



Deboard Rules

- Do not enter or work inside, if anyone 18 or younger is inside without an adult present (clients, babysitters, etc. as long as 18 or older), you may enter and work if inside is empty. If anyone 18 or younger comes in while you are inside, if they do not have an adult with them, you must leave immediately and contact the office.
- No alcohol. No profanity. No smoking on Job site. No loud music (use of ear buds or music volume at a minimum). No Dirty Shoes – Clean shoes, shoe booties or socks only.
- Respect other Subcontractors' and Homeowners' property at all times. Do not enter any areas of the home that are not included in the scope of work unless otherwise requested from the client or J&R Construction.
- Shirt must be worn at all time (NO TANK TOPS) – No vulgar or offensive slogan on shirts!
- Report any defects, safety issues, accidents, or concerns IMMEDIATELY to J&R Construction.
- Clean up after yourself and recycle when possible. No use of clients' tools or supplies EVER.
- At the end of the day the jobs site must be clean enough for a 3-year-old to walk into.
- If it doesn't look right or match, DO NOT install it. Ask questions before proceeding.
- If you spill it, clean it up immediately. Don't leave it to dry or to be cleaned by someone else at a later date.
- If we haven't done our part to protect appliances, tubs, tile, windows, or anything that is going to remain during the remodel process, please bring to our attention so that we can address it immediately.
- After you install – cover for protection (exampled – wood floors, tubs, vanities) until we move to next phase of project and that area no longer needs special protection.
- If you break or damage anything, contact J&R Construction immediately!

PROJECT SCOPE SUMMARY

- Construct a new detached two-car garage with attached lawn mower storage.
- Build a finished second-floor office/flex space with a half bath and unfinished attic storage.
- Complete all site preparation, excavation, reinforced concrete foundations, CMU stem walls, and concrete slab construction.
- Install a full brick exterior with architectural details to complement the existing residence.
- Complete framing, roofing, windows, exterior doors, garage doors, and weatherproofing.
- Install plumbing, electrical, insulation, and a mini-split HVAC system serving the finished second floor.
- Complete interior finishes including drywall, painting, finished carpentry, flooring, and half bath fixtures.
- Perform final grading, cleanup, inspections, system testing, and homeowner walkthrough.

GENERAL CONDITIONS / PROJECT MANAGEMENT

- Obtain required permits and coordinate all required inspections.
- Verify field measurements and existing site conditions prior to construction.
- Coordinate project scheduling, subcontractors, material procurement, and deliveries.
- Maintain a safe, clean, and organized jobsite throughout construction.
- Provide temporary site protection and erosion control as required.
- Coordinate utility connections throughout construction.
- Remove construction debris throughout each phase of the project.

SITE PREPARATION

- Layout the new detached garage in accordance with approved plans.
- Excavate for foundations, utilities, and concrete slabs.
- Prepare and compact the building pad and subgrade.
- Install foundation drainage system as required.
- Backfill foundations and rough grade around the structure.
- Grade site to provide positive drainage away from the building.

CONCRETE

- Excavate and construct reinforced concrete footings in accordance with approved plans.
- Install stair-stepped reinforced concrete footings as required to accommodate existing grade changes.
- Install compacted stone base, vapor barrier, and slab reinforcement.
- Install rigid insulation at the interior of CMU stem walls and beneath the concrete slab as specified.
- Install reinforced concrete slab for the two-car garage and attached lawn mower storage area.
- Finish concrete slabs ready for framing. Slick finish, sealed and cut control joints.
- Note-Order will be Footer, Block, Framing dried in, then poured concrete.

MASONRY

- Construct reinforced CMU stem walls in accordance with approved plans and applicable building codes.
- Fully slush CMU stem walls as required by code and structural requirements along with anchor bolts.
- Install full brick veneer to match the existing residence.
- Install decorative soldier courses to match the existing home.
- Install exterior quoins and masonry details to complement the existing architecture.
- Install all required masonry ties, flashing, reinforcement, and sealants.

FRAMING

- Frame the detached two-car garage, attached lawn mower storage area, interior stairwell, second-floor office/flex space, half bath, and unfinished attic storage areas.
- Install engineered beams, structural framing, floor systems, and roof framing in accordance with the approved plans.
- Frame openings for windows, exterior doors, and overhead garage doors.
- Construct the interior staircase.
- Install roof and wall sheathing.
- Install weather-resistant barrier.
- Install all required backing and blocking for future cabinetry, fixtures, handrails, and accessories.

ROOFING

- Install ice and water shield where required.
- Install roofing underlayment.
- Install asphalt shingles.
- Install flashing, drip edge, ridge vent, soffit, fascia, and gutters.
- Install downspouts.

WINDOWS & EXTERIOR DOORS

- Install energy-efficient windows throughout the second-floor office/flex space.
- Install insulated exterior service door.
- Install one double overhead garage door and one single overhead garage door serving the lawn mower storage area.
- Install garage door openers complete with wall controls, wireless remotes, and exterior keypad.
- Install exterior trim and weatherproof all openings.

BUILDING ENVELOPE

- Install weather-resistant barrier over exterior wall sheathing.
- Install flashing around windows, doors, and roof penetrations.
- Seal all exterior penetrations for improved weather resistance and energy efficiency.
- Install frieze board and complete exterior trim details.
- Complete exterior caulking and weatherproofing.

PLUMBING

- Install plumbing rough-in for the second-floor half bath.
- Install water supply, drain, waste, and vent piping.
- Install half bath.
- Install toilet, vanity, sink, faucet, and plumbing trim in the second-floor half bath.
- Test plumbing system upon completion.

HVAC

- Install mini-split heating and cooling system serving the finished second-floor office/flex space.
- Install refrigerant lines, condensate drain, and electrical disconnect.
- Start up, test, and verify proper operation of the HVAC system.

ELECTRICAL

- Install new electrical service and panel as required.
- Rough-in wiring throughout the garage, lawn mower storage area, stairwell, second-floor office, hallway, half bath, and unfinished attic storage areas.
- Provide wiring for garage door openers.
- Provide electrical connection for the mini-split HVAC system.
- Install LED recessed lighting throughout the garage.
- Install LED recessed lighting throughout the second-floor office, hallway, half bath, and stairwell.
- Install lighting within the unfinished attic storage areas.
- Install ceiling fans in the second-floor office and flex space.
- Install dimmer switches and three-way switching where shown on the plans.
- Install receptacles, switches, and cover plates throughout the garage, lawn mower storage area, and second-floor finished spaces in accordance with current electrical code.
- Install exterior light fixtures at entry doors.
- Install smoke and carbon monoxide detectors as required by code.
- Test all electrical systems.

INSULATION

- Install Batt insulation throughout all exterior walls.
- Install floor insulation beneath the finished second-floor office/flex space.
- Install roof insulation above the finished second floor and unfinished attic storage areas.
- Air seal all exterior wall and ceiling penetrations.

DRYWALL

- Install drywall throughout the garage, stairwell, second-floor office, half bath, and finished hallway using glue-and-screw installation methods.
- Tape, finish, sand, and prepare all drywall surfaces for paint.
- Finish garage walls and ceilings as specified.

FINISHED CARPENTRY

- Install interior doors throughout the finished second-floor spaces.
- Install baseboards, window trim, and door casing throughout finished areas on both levels.
- Install finished LVP stair treads, risers, handrails, and guardrails.
- Install closet shelving where applicable.
- Install vanity and countertop in the second-floor half bath.
- Install sink, faucet, and plumbing trim.
- Install bathroom mirror and accessories if included.
- Install all interior door hardware.
- Install bathroom accessories.
- Install garage door hardware and opener accessories.

PAINTING

- Prime and paint (2 coats) all drywall, ceilings, interior doors, trim, and finished carpentry throughout the garage, stairwell, second-floor office, hallway, and half bath.
- Complete final paint touch-ups after finish installations.

FLOORING

- Leave the garage and lawn mower storage area as finished concrete.
- Install finished flooring throughout the second-floor office, hallway, half bath, and finished stair treads.
- Install flooring transitions and finish trim as required.

FINAL COMPLETION

- Complete final grading around the building and verify positive drainage away from the foundation.
- Restore disturbed lawn areas as required.
- Remove all construction debris and clean interior and exterior finished surfaces.
- Complete final inspections and address any punch-list items.
- Demonstrate the operation of the garage doors, garage door openers, plumbing, electrical, and HVAC systems.
- Deliver applicable manufacturer warranties, product information, and maintenance recommendations.
- Conduct a final walkthrough with the homeowner.