

McMillan Scope of Work

1. GENERAL DESCRIPTION

Provide labor, materials, and supervision to complete exterior porch repairs and interior renovations including kitchen island modification, custom built-ins, and master suite improvements. Work will be completed in phases, with priority given to the front porch.

2. PHASE 1 – FRONT PORCH

2.1 Demolition

- Remove existing damaged or failing porch components as required
- Keep porch surroundings unless cracking, only demolish top
- Demolish existing front walkway

2.2 Structural and Framing

- Evaluate existing porch framing and structural components
- Repair or replace deficient framing as required to meet current standards

2.3 Columns and Trim

- Furnish and install new columns to match existing rear columns (material and size to be confirmed)
- Modify or replace beam wraps and trim as required
- Repair or replace soffit as needed

2.4 Concrete and Masonry

- Repair porch slab cracking where feasible
- Install control joints as required
- Pour concrete base/slab for paver installation
- Install curved steps with pavers
- Install new porch with pavers in herringbone
- Form and pour new front walkway (layout to be finalized)
- Install curved, reinforced, brick walls in front of porch for planters
- Regrade surrounding area to improve drainage away from structure

2.5 Drainage and Site Work

- Adjust grading to direct water away from porch and adjacent areas
- Install retaining walls

3. INTERIOR SCOPE OF WORK

3.1 Built-In Display Cabinet (Upstairs Hallway)

Framing and Installation

- Frame and install custom built-in cabinets

Cabinetry

- Furnish and install glass-front cabinet system
- Provide sealed enclosure with tight-latching or gasketed doors to minimize insect intrusion

3.2 Kitchen Island Modification

Cabinetry

- Install new island cabinetry to accommodate 36" cooktop
- Provide green cabinet finish (door style to be selected by client)
- Install drawer bases for storage on designated side
- Install one additional outlet on kitchen island

Countertops

- Furnish and install black butcher block countertop
- Source via prefab or custom fabrication based on availability and lead time

Appliances

- Coordinate with existing JennAir downdraft cooktop (client-provided)
- Install new cooktop (client-provided)

3.3 Master Bathroom Renovation

Demolition

- Remove existing hot tub, shower, and associated finishes

Cabinetry

- Furnish and install full height pull out cabinet

Framing and Layout

- Frame new wall layout as required for updated bathroom configuration
- Construct niche in shower and by toilet
- Frame double arched doorway for shower

Shower Construction

- Construct walk-in shower with curb
- Install waterproofing system per manufacturer specifications
- Install and grout shower floor tile
- Install and grout blue shower wall tile on shower head wall and side walls (client-provided)
- Install and grout accent shower wall on wall with doors
- Install and grout shower niche tile

Flooring

- Install heated floor system (reuse existing circuit if feasible)
- Install client supplied tile and grout

Fixtures and Finishes

- Install client-provided vanity components (antique pieces)
- Install quartz countertop on chosen vanity cabinets
- Install plumbing fixtures (client-provided), tile (some client-provided), and finishes (some client-provided) per finalized design
- Install decorative light fixture over tub (client-provided)
- Install vanity sconces (client-provided)
- Install can fan in shower placement in plan
- Install exhaust fan over toilet
- Install two cans in shower
- Install 6 cans in bathroom
- Remove existing light switches by entry door
- Install double light switch by entry door refer to plan for placement
- Install outlet next to entry light switch
- Install outlet behind commode for bidet
- Install outlet over vanity next to new pull out cabinet
- Install two switches by commode for light and fan
- Install two switches by shower for light and fan

3.4 Master Closet Reconfiguration

Demolition

- Remove existing closet walls and components as required

Framing

- Frame new closet layout to improve storage and functionality
- Frame two new arched closet doorways
- Incorporate dormer space where feasible

Closet System

- Install closet system

Fixtures & Finishes

- Install drywall, trim, and finishes to match adjacent areas
- Inspect and repair crown molding
- Install four cans in closet
- Install one switch by closet entry
- Install outlet next to switch

- Possible installation of second switch and decorative light
- Install ceiling fan over middle of bedroom
- Install switch for ceiling fan by bedroom entry door

3.5 Master Bedroom Flooring

Demolition

- Remove existing LVT flooring

Subfloor Preparation

- Inspect and repair subfloor to eliminate movement and squeaks by installing screws
- Fasten and level subfloor as required

Flooring Installation

- Install new client supplied flooring and quarter round

4. EXCLUSIONS

- Landscaping, planting, and irrigation by others
- Final design selections not outlined above
- Unforeseen structural repairs not visible at time of estimate

5. ALLOWANCES / SELECTIONS REQUIRED

- Cabinet door style (kitchen island)
- Countertop selections for bathroom (450)
- Closet system (5000)
- Closet and bedroom light switches

6. SCHEDULE

- Phase 1 (Front Porch) to be scheduled and initiated first
- Interior phases to follow based on material lead times and design approvals

7. NOTES

- All work to comply with applicable building codes and standards
- Any additional work or changes to the scope will require a written change order
- Client to provide access to property and utilities during construction